ADDENDUM NUMBER 1 2025 ASPHALT RESURFACING PROJECT NUMBER PW-2025-01 04/24/2025

The following changes, modifications, and/or clarifications to the project documents are a part, thereof, and change the original documents only in the manner and to the extent stated.

- 1. Bidders are reminded to comply with all the requirements for bidding as enumerated in the Project Manual, INCLUDING ACKNOWLEDGEMENT OF THE RECEIPT OF THIS ADDENDUM ON THE BID FORM.
- 2. Reference is made to the Bid Form: Remove old Bid Form and replace with the attached new Revised Bid Form Addendum 1. Modifications include correcting the "Unit" for line items 7 and 8 to square yards, adding line item 18 for reconstructing the catch basin lid on 13-0003 (not the entire structure) and adding Traffic Control as a lump sum pay item for Bid Alternate BA1-6.
- 3. Question was asked: Would the Town consider replacing the sign instead of the jack and bore of two sticks of pipe? The response is: The Town had considered replacing the sign but decided not to replace the sign and do the jack and bore instead.
- 4. Question was asked: Is railroad insurance required? The response is: At this time, all work performed will be in the Town's right-of-way and we will not be requiring railroad insurance.
- 5. Question was asked: Is the intent on Sheet 13-0003 for the replacement of the catch basin lid or the entire catch basin. The answer is: The intent is for the catch basin lid to be replaced only. A line item has been added to the revised bid form as per item 2 above.
- 6. Question was asked: Can a line item be added for replacing drainage structures for the existing structures where pipes are being replaced. The response is: We do not anticipate drainage structures needing to be replaced. If there is existing damage that the contractor demonstrates to the Engineer and Owner prior to removing pipe that in the opinion of the Engineer and Owner requires replacement, this would be discussed and negotiated as part of a special allowance or change order. We understand that some reconstruction will be required as we are changing from CMP to RCP, and the cost for the reconstruction should be placed under the stormwater pipe's line items.

END OF ADDENDUM NO. 1

| BIDDER acknowledges receipt of the following ADDENDUM: |
|--|
|--|

BIDDER agrees to perform all the work described in the CONTRACT DOCUMENTS for the following unit prices or lump sum including all applicable taxes and fees:

Addendum 1: BID SCHEDULE

| Γ | Addendum 1: DID | Estimate | | Unit | Total |
|-----|---|----------|----|-------------|-------------|
| No. | Item | Quantity | | Price | Price |
| 1. | Traffic Control, complete, Pay Item 150-1000 | 1 | LS | | \$ |
| 2. | Grading, complete, Pay Item 210-0100 | 1 | LS | | \$ |
| 3. | Recycled Asph Conc 9.5 mm Superpave, Type II, GP 2 only, Incl Bitum Matl & Lime, Pay Item 402-3103 | 894 | TN | | \$ |
| 4. | Recycled Asph Conc 12.5 mm Superpave, GP 2 only, Incl Polymer Mofified Bitum Matl & Lime, Pay Item 402-4510 | 1,737 | TN | | \$ |
| 5. | Recycled Asph Conc 19 mm Superpave, Type II, GP1 or GP 2, Incl Bitum Matl & Lime, Pay Item 402-3190 | 2,528 | TN | | \$ |
| 6. | Recycled Asph Conc 25 mm Superpave, Type II, GP1 or GP 2, Incl Bitum Matl & Lime, Pay Item 402-3121 | 3.4 | TN | | \$ |
| 7. | Mill Asph Conc Pvmt 3.5" Depth, Pay Item 432-0214 | 10,813 | SY | | \$ |
| 8. | Mill Asph Conc Pvmt 4" Depth, Pay Item 432-0216 | 12,139 | SY | | \$ |
| 9. | Tack Coat, Pay Item 413-0750 | 1,598 | GL | | \$ |
| 10. | Thermoplastic Solid Traf Stripe, 6" yellow, Pay Item 653-2602 | 580 | LF | _ | \$ |
| 11. | Thermoplastic Solid Traf Stripe, yellow, Pay Item 653-6006 | 16 | SY | | \$ |
| 12. | Thermoplastic Solid Traf Stripe, 24" white, Pay Item 653-1704 | 100 | LF | | \$ |
| 13. | Raised PVMT Markers Type 1. Pay Item 654-1001 | 28 | EA | | \$ |
| 14. | Stm Dr Pipe 18, H 1-10 Pay Item 550-1180 | 58 | LF | | \$ |
| 15. | Stm Dr Pipe 36, H 1-10 Pay Item 550-1360 | 30 | LF | | \$ |
| 16. | Stm Dr Pipe 42, H 1-10 Pay Item 550-1420 | 33 | LF | | \$ |
| 17. | Jack and Bore Pipe 18" Pay Item 615-2540 | 16 | LF | | \$ |
| 18. | Reconstruction Catch Basin Lid GP1(Sheet 13-0003) Pay Item 611-3000 | 1 | LS | | \$ |
| 19. | Special Allowance, complete. | 1 | LS | \$20,000.00 | \$20,000.00 |

| Total of Base Bid pl | lus Allowance - 🛭 | \$ | |
|----------------------|-------------------|----|--|
| Total of Base Bid pl | lus Allowance - 🗄 | \$ | |

Addendum 1: BID ALTERNATE 1 SCHEDULE

| | | Estimate | | Unit | Total |
|-------|---|----------|------|-------|-------|
| No. | Item | Quantity | Unit | Price | Price |
| BA1-1 | Recycled Asph Conc 12.5 mm Superpave, GP 2 only, Incl Polymer Modified Bitum Matl & Lime, Pay Item 402-4510 | 82 | TN | | \$ |
| BA1-2 | Recycled Asph Conc 19 mm Superpave, Type II, GP1 or GP 2, Incl Bitum Matl, Pay Item 402-3192 | 82 | TN | | \$ |
| BA1-3 | Mill Asph Conc Pvmt 4" Depth, Pay Item 432-0216 | 738 | SY | | \$ |
| BA1-4 | Tack Coat, Pay Item 413-0750 | 45 | GL | | \$ |
| BA1-5 | Thermoplastic Solid Traf Stripe, 24" white, Pay Item 653-1704 | 17 | LF | | \$ |
| BA1-6 | Traffic Control, complete, Pay Item 150-1000 | 1 | LS | | \$ |

| Total of Bid Alternates - \$ | |
|---|--|
| TOTAL CONTRACTED AMOUNT: \$(Base Bid, Allowances, and Alternates) | |
| limitations, based on prices bid. | project scope, as necessary to meet project budget usiness License (Occupational Tax Certificate) by Georgia Secretary of State. |
| Respectfully Submitted: | |
| Signature | Company's Legal Name |
| Printed Name | Address |
| Title | City, State, Zip Code |

License No.

Date