

ADDENDUM NUMBER 1
2026 ASPHALT RESURFACING
PROJECT NUMBER PW-2026-01
04/16/2026

The following changes, modifications, and/or clarifications to the project documents are a part, thereof, and change the original documents only in the manner and to the extent stated.

1. Bidders are reminded to comply with all the requirements for bidding as enumerated in the Project Manual, **INCLUDING ACKNOWLEDGEMENT OF THE RECEIPT OF THIS ADDENDUM ON THE BID FORM.**
2. Question was asked: Do you require manhole adjustments? If so, is adjusting with a riser ring acceptable or do we need to adjust with concrete? The answer is: No utility adjustments are anticipated with this project, including adjustment of manholes to grade. The intent is for a general resurfacing to mill and inlay to match existing. It is requested that the asphalt surface be a smooth transition around all manholes and valves to ensure adequate/positive drainage, as needed.
3. Question was asked: Is there a special type of scope in which the grading complete item is expected? The answer is: For 210-0100 Grading Complete, this item was included for any ancillary tasks needed included cleaning of any street debris, sod installation for any areas impacted during construction/stage activities, etc.

END OF ADDENDUM NO. 1