


SUMMARY OF QUANTITIES

ROADWAY QUANTITIES										
DESCRIPTION	315-1012 STABILIZED BASE COURSE, 12 IN, INCL MATERIAL	315-1010 STABILIZED BASE COURSE, 10 IN, INCL MATERIAL	402-3103 RECYCLED ASPH CONC 9.5 MM SUPERRAVE, TYPE II, GP 2 ONLY, INCL BITUM MATL & H LIME	402-3190 RECYCLED ASPH CONC 19 MM SUPERRAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	402-3121 RECYCLED ASPH CONC 25 MM SUPERRAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	432-0206 MILL ASPH CONC PVMT, 1 1/2 IN DEPTH	413-0750 TACK COAT	315-1000 PORTLAND CEMENT	UNIT	SY
	585	19,691	2,696	129	124	684	339	558	TN	585
	-	7713	894	-	12	549	33	212	GL	7713
LAURELWOOD DRIVE	-	-	409	-	109	-	298	-	TN	409
FOXFORDRUN	-	6822	750	-	-	-	-	188	GL	6822
RIDGE ROAD	-	3727	410	-	-	-	-	102	GL	3727
LAUREL LAKE ROAD	-	1429	157	-	-	-	-	39	GL	1429
STRAWBERRY LANE	-	-	75	129	3	135	8	16	GL	75
TYRONE ROAD	585	-	-	-	-	-	-	-	GL	585

BID ALTERNATE #1	
231-1250	MISCELLANEOUS CONSTRUCTION
EA	
I	

SIGNING AND MARKING ITEMS

PAY ITEM	DESCRIPTION	UNITS	TOTAL QTY	LAURELWOOD DRIVE	FOXWOOD RUN	RIDGE ROAD	LAUREL LAKE ROAD	STRAWBERRY LANE	TYRONE ROAD
653-0100	THERMOPLASTIC PVMT MARKING, RR/HWY CROSSING SYMBOL	EA	1	-	-	-	-	-	1
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	495	-	-	-	-	-	495
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	902	300	100	100	100	100	202
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	88	32	10	10	10	14	12
653-6006	THERMOPLASTIC TRAF STRIPING, YELLOW	SY	60	-	-	-	-	-	60
654-1001	RAISED PVMT MARKERS TP 1	EA	48	12	4	4	4	4	20



REVISION DATES	
03/13/24	
04/02/24	

SUMMARY QUANTITIES	
TOWN OF TYRONE	
2024 ASPHALT RESURFACING	
CHECKED:	DATE:
BACKCHECKED:	DATE:
CORRECTED:	DATE:
VERIFIED:	DATE:
DRAWING No. 06-0001	